

Nr. Crt.	DENUMIRE LUCRARE	U.m.	Cant
ECHIPAMENTE CENTRALA TERMICA			
1	Centrala termica 400 kw in condensatie (2 CT X 200 kw)	ans	1.00
2	Modul automatizare cascada, senzori nivel, limitatori de presiune, cabluri, console, module comunicatie	ans	1.00
3	Kit de evacuare	ans	1.00
4	Boiler 300 litri	buc	1.00
5	Rezistenta electrica, flansa emailata	buc	1.00
6	Butelie amestec	buc	1.00
7	Pompa boiler H-8MCA, 6MCH	buc	1.00
8	Pompa ventilconvectoare H-4MCA, 6.6MCH	buc	1.00
9	Pompa aeroterme H-4MCA, 6.6MCH	buc	1.00
10	Pompa radiatoare hala H-8MCA, 3.9MCH	buc	1.00
11	Pompa radiatoare corp administrativ H-8MCA, 3.9MCH	buc	1.00
12	Pompa injectie cazan H- 3MCA, 12MCH	buc	1.00
13	Vas expansiune incalzire 150L	buc	2.00
14	Vas expansiune ACM 20L	buc	1.00
15	Regulator gaz 1 1/4"	buc	2.00
16	Detector gaz (Detector gaz metan, Tecnogas, CD 68, cu fir)	buc	1.00
MATERIALE MONTAJ CENTRALA TERMICA			
1	Teava zincata, teava ppr, robineti, clapate, teuri, coturi, supape de sens, izolatii, mufe, niple, racorduri sisteme de prindere si ancorare	ans	1.00
MATERIALE LEGATURI ELECTRICE SI AUTOMATIZARE IN CENTRALA TERMICA			
1	Tablouri electrice, contactoare, sigurante, cabluri	buc	1.00

MANOPERA MONTAJ CENTRALA TERMICA			
1	Demontare si manipulare Centrala Termica existente fonta, Demontare si manipulare Boiler 200 litri, Demontare cablaj electric, Demontare tevi gaz, Demontare distributie tevi incalzire + apa calda menajera + apa rece	ans	1.00
2	Spalare instalatie incalzire existenta	buc	4.00
3	Probe presiune instalatie incalzire existenta	buc	4.00
4	Montaj centrale termice, echipamente conexe si materiale necesare montarii	ans	1.00
5	Reparatii instalatii termice interioare existente	ans	1.00
7	Manopera instalatii electrice	ans	1.00
8	Manopera legaturi instalatie gaz existenta	ans	1.00

9	Pretul include cheltuieli de transport materiale si echipamente, diurna si cazare si cheltuieli de transport personal calificat		
----------	---	--	--

1	Proiectare conform normelor in vigoare	ans	1.00
----------	--	-----	------

1	PIF si autorizari ISCIR	buc	2.00
----------	-------------------------	-----	------