

LISTA cu cantitatile de lucrari pe categorii de lucrari

Obiect: 01 LUCRARI DE PARDOSELI

Categorie: 01 RAR TIMIS

| | | | | | [ron] |
|---|------------------|-----|---------------|----------------|---------------|
| Nr. | Capitol lucrari | U/M | Cantitatea | Pretul unitar | Valoare |
| Crt. | Simbol | | | a)materiale | |
| | Denumire resursa | | | b)manopera | |
| | Observatii | | | c)utilaj | |
| | Corectii | | | d)transport | |
| | Liste Anexe | | | Total(a+b+c+d) | |
| 1 | RPCT20A1 82 | MP | 335.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| DESFACEREA PARDOSELILOR DIN CIMENT TURNATE PE LOC SCLIVISITE ROLATE MOZAIcate * | | | | | |
| 2 | DC02XA 91 | M | 152.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| TAIEREA CU MASINA CU DISCURI DIAMANTATE A ROSTURILOR LA IMBRACAM.BET.CIM.,COLMATAREA CU MASTIC BIT. | | | | | |
| ASIM. LARGIRE FISURI PARDOSELI | | | | | |
| 3 | H1E03A 82 | M | 152.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| ETANSARE ROST.CONTRACTIE INTRE BLOCURI CONSTR.MASIVE DIN BETON CU BANDA DIN PVC. | | | | | |
| ASIM. MATARE FISURI PARDOSEALA | | | | | |
| 4 | 7329433 | KG | 76.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| MASA DE ETANSARE EPOXI | | | | | |
| 0.5 KG/M | | | | | |
| 5 | RPCK45B 09 | MP | 335.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| STRAT SUPORT PT. PARDOSELI CU MORTAR EPOXI | | | | | |
| 6 | IZN01XF 91 | MP | 620.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| PREGATIREA SUPRAF.DE BET.PT.APLICAREA CAPTUSELILOR EPOXIDICE IN PARDOSELI | | | | | |
| 7 | IZA12A1 82 | MP | 620.00000 | | |
| | | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% |
| DESPRAF DEGRESARE SUPRAF BETON METAL IN VEDEREA APLICARII PROT ANTICOROZ | | | | | |

| Nr. Crt. | Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe | U/M | Cantitatea | Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d) | Valoare |
|--|--|------------------|---------------|---|---------|
| 8 | H1E22A1 82 | MP | 620.00000 | | |
| | | Sp.mat: -100.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR. | | | | | |
| STRAT GRUND | | | | | |
| 9 | 7801847 | KG | 310.00000 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| GRUND EPOXIDIC (EPOMA PRIMER) | | | | | |
| 0.5 KG/MP | | | | | |
| 10 | H1E22A1 82 | MP | 620.00000 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR. | | | | | |
| SUPRAFATA DE UZURA EPOXI | | | | | |
| 11 | 7800551 | KG | 1,240.00000 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| PARDOS. EPOXI BICOMP. RAL 7040 GRI | | | | | |
| 2 KG/MP | | | | | |
| 12 | 9999446 | KG | 682.00000 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| NISIP DE CUART | | | | | |
| 1.1 KG/MP | | | | | |
| 13 | TRI1AA01A1 82 | TONE | 2.89400 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| ARCAREA MATERIALELOR,GRUPA A-GRELE SI MARUNTE,PRIN ARUNCARE RAMPA-VAGON CATEG.1 | | | | | |
| | | | | \$ | |
| 14 | TRA01A20 82 | TONE | 2.89400 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELOR CU AUTOBASculANTA PE DIST.= 20 KM. | | | | | |
| | | | | \$ | |
| 15 | TRI1AC13E2 82 | TONE | 2.89400 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| DESCARCARE MAT.GR.C-AMBALATE,10-50 KG DEPLAS.PRIN PURTARE PINA LA 10M,ASEZ..AUTO-RAMPA,TEREN CTG.2 | | | | | |
| | | | | \$ | |
| 16 | TRB05B23 82 | TONE | 2.89400 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |
| TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 30M | | | | | |
| | | | | \$ | |

| Nr. | Capitol lucrari | U/M | Cantitatea | Pretul unitar | Valoare |
|------|------------------|-----|------------|----------------|---------|
| Crt. | Simbol | | | a)materiale | |
| | Denumire resursa | | | b)manopera | |
| | Observatii | | | c)utilaj | |
| | Corectii | | | d)transport | |
| | Liste Anexe | | | Total(a+b+c+d) | |

| | | | | | |
|----|--------------|---------------|---------------|---------------|--|
| 17 | TRA01A20P 82 | TONE | 1.75000 | | |
| | | Sp.mat: 0.00% | Sp.man: 0.00% | Sp.uti: 0.00% | |

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=20 KM

\$

| | | | | | | |
|--------------------------------|------|-------------------|------|------|------|------|
| Cheltuieli directe | | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| Alte cheltuieli directe | | | | | | |
| Contrib. asig. munca | | 0.0225% | 0.00 | | | 0.00 |
| TOTAL CHELT. DIRECTE | | | 0.00 | 0.00 | 0.00 | 0.00 |
| Cheltuieli indirecte | Io = | 0.0000% x To | | | | 0.00 |
| Profit | Po = | 0.0000% x (To+Io) | | | | 0.00 |
| TOTAL GENERAL categorie | Vo = | To+Io+Po | | | | 0.00 |