

Formular F3

Obiectiv: RAR

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: LUCRARI DE REPARATII

Categorie: RAR OLT

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol			a) materiale	
	Denumire resursa			b) manopera	
	Observatii			c) utilaj	
	Corectii			d) transport	
	Liste Anexe			Total(a+b+c+d)	
1	RPCT20A1 82	MP	180,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
DESFACEREA PARDOSELILOR DIN CIMENT TURNATE PE LOC SCLIVISITE ROLATE MOZAIcate *					
2	DC02XA 91	M	180,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
TAIEREA CU MASINA CU DISCURI DIAMANTATE A ROSTURILOR LA IMBRACAM.BET.CIM.,COLMATAREA CU MASTIC BIT.					
SIM. LARGIRE FISURI PARDOSELI					
3	H1E03A 82	M	180,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
ETANSARE ROST.CONTRACTIE INTRE BLOCURI CONSTR.MASIVE DIN BETON CU BANDA DIN PVC.					
ASIM. MATARE FISURI PARDOSEALA					
4	7329433	KG	45,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
MASA DE ETANSARE EPOXI					
0.5 KG/M					
5	RPCK45B 09	MP	180,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
STRAT SUPORT PT. PARDOSELI CU MORTAR EPOXI					

5	0000701		KG		1.080,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
STRAT INTERMEDIAR EPOXI					
SUPL. GROSIME MEDIE 4MM; 200MPX3MMX1,8 KG/MM					
6	IZN01XF 91		MP		200,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PREGATIREA SUPRAF.DE BET.PT.APLICAREA CAPTUSELILOR EPOXIDICE IN PARDOSELI					
7	IZA12A1 82		MP		200,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
DESPRAF DEGRESARE SUPRAF BETON METAL IN VEDEREA APLICARII PROT ANTICOROZ					
8	H1E22A1 82		MP		200,00000
			Sp.mat: - 100.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR.					
STRAT GRUND					
9	7801847		KG		100,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
GRUND EPOXIDIC (EPOMA PRIMER)					
0.5 KG/MP					
10	H1E22A1 82		MP		200,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR.					
JPRAFATA DE UZURA EPOXI					
11	7800551		KG		400,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PARDOS. EPOXI BICOMP. RAL 7040 GRI					
2 KG/MP					
12	9999446		KG		220,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
NISIP DE CUART					
1.1 KG/MP					
13	TRI1AA01A1 82		TONE		2,66300
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI MARUNTE,PRIN ARUNCARE RAMPA-VAGON CATEG.1					
					\$

14	TRA01A20 82	TONE		2,66300
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%

TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELOR CU AUTOBASCULANTA PE DIST.= 20 KM. \$

15	TRI1AC13E2 82	TONE		2,66300
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%

DESCARCARE MAT.GR.C-AMBALATE,10-50 KG DEPLAS.PRIN PURTARE PINA LA 10M,ASEZ..AUTO-RAMPA,TEREN CTG.2 \$

16	TRB05B23 82	TONE		2,66300
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 30M \$

17	TRA01A20P 82	TONE		2,52000
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=20 KM \$

Cheltuieli directe		0,00	0,00	0,00	0,00	0,00
Coeficient actualizare		-1,00	-1,00	-1,00	0,00	
Valoare actualizare		0,00	0,00	0,00	0,00	
Total cheltuieli directe actualizat		0,00	0,00	0,00	0,00	0,00
Alte cheltuieli directe						
C.A.S.	0,0000%		0,00			0,00
C.A.S.S.	0,0000%		0,00			0,00
Aj.somaj	0,0000%		0,00			0,00
Acc. munca, boli profes.	0,0000%		0,00			0,00
Contr.Concedii Medicale	0,0000%		0,00			0,00
Contrib. asig. munca	0,0000%		0,00			0,00
Fond garantare salarii	0,0000%		0,00			0,00
TOTAL CHELT. DIRECTE		0,00	0,00	0,00	0,00	0,00
Cheltuieli indirecte	Io =	0,0000%	x To			0,00
Profit	Po =	0,0000%	x (To+Io)			0,00
TOTAL GENERAL categorie Vo =			To+Io+Po			0,00