

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiect: INVESTITII

Categorie: RAR IALOMITA

[ron]

Nr.	Capitol lucrari	U/M	Cantitatea	Pretul unitar	Valoare
Crt.	Simbol Denumire resursa Observatii Corectii Liste Anexe			a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	
1	RPCT20A1 82	MP	280,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
DESFACEREA PARDOSELILOR DIN CIMENT TURNATE PE LOC SCLIVISITE ROLATE MOZAIcate *					
2	DC02XA 91	M	214,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
TAIEREA CU MASINA CU DISCURI DIAMANTATE A ROSTURILOR LA IMBRACAM.BET.CIM.,COLMATAREA CU MASTIC BIT.					
DIM. LARGIRE FISURI PARDOSELI					
3	H1E03A 82	M	214,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
ETANSARE ROST.CONTRACTIE INTRE BLOCURI CONSTR.MASIVE DIN BETON CU BANDA DIN PVC.					
ASIM. MATARE FISURI PARDOSEALA					
4	7329433	KG	107,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	
MASA DE ETANSARE EPOXI					
0.5 KG/M					
5	RPCk45B 09	MP	400,00000		
		Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%	

STRAT SUPORT PT. PARDOSELI CU MORTAR EPOXI

6	0000701		KG		1.971,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
STRAT INTERMEDIAR EPOXI					
SUPL. GROSIME MEDIE 3MM; 365 MPX3MMX1,8 KG/MM					
7	IZN01XF 91		MP		400,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PREGATIREA SUPRAF.DE BET.PT.APLICAREA CAPTUSELILOR EPOXIDICE IN PARDOSELI					
8	IZA12A1 82		MP		400,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
DESPRAF DEGRESARE SUPRAF BETON METAL IN VEDEREA APLICARII PROT ANTICOROZ					
9	H1E22A1 82		MP		400,00000
			Sp.mat: - 100.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR.					
STRAT GRUND					
10	7801847		KG		200,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
GRUND EPOXIDIC (EPOMA PRIMER)					
0.5 KG/MP					
11	H1E22A1 82		MP		400,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PROTEJAREA CU RASINI EPOXIDICE A SUPRAF.DE BETON-CONSTR.HIDRO LA UZURA SI CAVITATIE;INCLIN.<20 GR.					
)PRAFATA DE UZURA EPOXI					
12	7800551		KG		800,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
PARDOS. EPOXI BICOMP. RAL 7040 GRI					
2 KG/MP					
13	9999446		KG		440,00000
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%
NISIP DE CUART					
1.1 KG/MP					
14	TR11AA01A1 82		TONE		4,33900
			Sp.mat: 0.00%	Sp.man: 0.00%	Sp.uti: 0.00%

INCARCAREA MATERIALELOR,GRUPA A-GRELE SI MARUNTE,PRIN ARUNCARE RAMPA-VAGON CATEG.1 \$

15 TRA01A20 82 TONE 4,33900
 Sp.mat: 0.00% Sp.man: 0.00% Sp.uti: 0.00%

TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELOR CU AUTOBASCULANTA PE DIST.= 20 KM. \$

16 TRI1AC13E2 82 TONE 4,33900
 Sp.mat: 0.00% Sp.man: 0.00% Sp.uti: 0.00%

DESCARCARE MAT.GR.C-AMBALATE,10-50 KG DEPLAS.PRIN PURTARE PINA LA 10M,ASEZ..AUTO-RAMPA,TEREN CTG.2 \$

17 TRB05B23 82 TONE 4,33900
 Sp.mat: 0.00% Sp.man: 0.00% Sp.uti: 0.00%

TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT,MATERIALE INCOMODE PESTE 25 KG DISTANTA 30M \$

18 TRA01A20P 82 TONE 2,14400
 Sp.mat: 0.00% Sp.man: 0.00% Sp.uti: 0.00%

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=20 KM \$

Contrib. asig. munca		0,0000%		0,00		0,00
Fond garantare salarii		0,0000%		0,00		0,00
TOTAL CHELT. DIRECTE				0,00	0,00	0,00
Cheltuieli indirecte	Io =	0,0000%	x To			0,00
			x			
Profit	Po =	0,0000%	(To+Io)			0,00
TOTAL GENERAL categorie Vo =			To+Io+Po			0,00